

15-019-19299.00.00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market; Room 2078

Wichita, Kansas 67202

API NUMBER

N/A

SWSENW

Sec/Twp/Rge 15-34-12E

3192'

feet from south section line

3688'

feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 33594

Lease/Well#

DEARMOND # OW-1

Operator: QUITO, INC.%MARK MCCANN

County

CHAUTAUQUA

Name & 4100 SE ADAMS RD. STE.C105

Well Total Depth 950' EST. feet

Address BARTLESVILLE, OK. 74006

Production Pipe: 5.5" Size Feet

Surface Casing: 7" Size Feet

AB oil well XXXXXXXX Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE

Lic. #

3097

Address: 19450 FORD ROAD CHANUTE, KANSAS 66720

Company to plug at: Hour: Day: 5 Month: 10 2005

Plugging proposal received from:

Company Name: Phone:

Were:

Plugging Proposal Received by:

Plugging attended by Agent: All XXXXXXXX Part

TECHNICIAN

None

Operations Completed: Hour: Day: 5 Month: 10 2005

Actual Plugging Report: DRILLED OUT AND FISH WOOD, ROCKS AND IRON FROM 145' TO

250' GOT ON SOMETHING THAT WOULD NOT DRILL. PERFORATED 5.5" PIPE AT 100'. SET RAG

PACKER AT 250' AND RAN .75" PIPE DOWN THE OUTSIDE TO 245', PUMPED 70 SACKS CEMENT

TO SURFACE. THE NEXT DAY THE 2" WAS ON A VACUUM, HOOKED TO THE 2" AND PUMPED

100 SACKS CEMENT AND THE WELL STARTED LOCKING UP AT 500 PSI, SHUT IN 2" PIPE.

Remarks: CONTROL# 20060013-001

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

TOM BILYEU / RON ROWE

TECHNICIAN

RECEIVED
OCT 17 2005
KCC WICHITA