

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21604-00-00
Spot: NWSENE Sec/Twnshp/Rge: 27-13S-30W
820 feet from N Section Line, 590 feet from E Section Line
Lease Name: F C BROOKOVER Well #: 4
County: GOVE Total Vertical Depth: 4610 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 155 N. MARKET, STE. 1020
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	275		

149 83

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/08/2005 6:30 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: JOHN ROBERTS Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 10/08/2005 8:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:


1st Plug at 2275' w/25 sxs.
2nd. Plug at 1425' w/100 sxs.
3rd. Plug at 325' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 
(TECHNICIAN)

NOV 01 2005

INVOICED
DATE 11-4-05
INV. NO 2006060703

RECEIVED
NOV 04 2005
KCC WICHITA