

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23102-00-00
Spot: SENENW Sec/Twnshp/Rge: 5-8S-24W
990 feet from N Section Line, 2310 feet from W Section Line
Lease Name: TEEL Well #: 3
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

125¹³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/31/2005 10:30 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 10/31/2005 12:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2050' w/25 sxs.
2nd. Plug at 1225' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED
DATE 11-4-05
INV NO 2006060698

RECEIVED
NOV 04 2005
KCC WICHITA

Form CP-2/3

NOV 01 2005