

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20706-00-00
Spot: N2S2SW Sec/Twnshp/Rge: 35-10S-33W
890 feet from S Section Line, 1330 feet from W Section Line
Lease Name: JAMES Well #: 1
County: THOMAS Total Vertical Depth: 4685 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	319		

\$152²⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/13/2005 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 10/13/2005 2:00 PM KCC Agent: HERB DEINES

Actual Plugging Report: _____ Perfs: _____
1st. Plug at 2650' w/25 sxs.
2nd. Plug at 1650' w/100 sxs.
3rd. Plug at 375' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

District: 04 Signed [Signature] (TECHNICIAN)

INVOICE
DATE 11-4-05
REV NO 2006060698

RECEIVED
NOV 04 2005
KCC WICHITA

Form CP-2/3

NOV 02 2005