

RECEIVED

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

NOV 01 2005

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

WELL PLUGGING RECORD KCC WICHITA
K.A.R. 82-3-117

Lease Operator: Dart Cherokee Basin Operating Co. LLC

Address: 211 W. Myrtle, Independence, Ks. 67301

Phone: (620) 331-7870 Operator License #: 33074

Type of Well: SWD Docket #: D-23422
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/26/2005 (Date)

by: Alan Dunning (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Arbuckle Depth to Top: 1500 Bottom: 1565 T.D. 1586
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 125-27032-00-00

Lease Name: Lavelly

Well Number: 4-C

Spot Location (QQQQ): NW - NW - NE - NE
5115 Feet from North / South Section Line

1155 Feet from East / West Section Line

Sec. 3 Twp. 31 S. R. 15 East West

County: Montgomery

Date Well Completed: 8/7/84

Plugging Commenced: 10/26/2005

Plugging Completed: 10/26/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	65'	7"	0	0
		0	1586'	4.5"	0	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Retrievable plug in casing a 1320'. Collapsed casing at 1290' making it impossible to retrieve plug.

Ran 2 3/8" tubing to 1315' feet and filled casing from bottom to top with cement. Pulled out tubing and topped off well with cement. A total of 125 sacks of 60/40 Poz Mix cement with 2% gel were used to plug this well.

Cut well head off below plow depth and restored location.

Name of Plugging Contractor: Consolidated Oil Well Services License #: 31440

Address: P.O. Box 884, Chanute, Ks. 66720

Name of Party Responsible for Plugging Fees: Dart Cherokee Basin Operating Co. LLC.

State of Kansas County, Montgomery, ss.

Tony Williams (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Tony Williams

(Address) 211 W. Myrtle, Independence, Ks. 67301

SUBSCRIBED and SWORN TO before me this 31st day of October, 20 05

LISA SHARTZER
Notary Public - State of Kansas
My Appt. Expires 5-26-06

Lisa Shartzer My Commission Expires: 5-26-06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

am