

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
NOV 02 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
Blanks must be Filled

Lease Operator: Deutsch Oil Company
Address: 107 N. Market, Suite 1115
Phone: (316) 267-7551 Operator License #: 3180
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: October 18, 2005 (Date)
by: Steve Pfeifer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 4388' Bottom: 4550' T.D. 4676'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-22,067-00-00
Lease Name: Eads
Well Number: #2-22
Spot Location (QQQQ): C - N/2 - SW - SE
990' Feet from North / South Section Line
1980' Feet from East / West Section Line
Sec. 22 Twp. 29 S. R. 14 East West
County: Pratt
Date Well Completed: 1/11/92
Plugging Commenced: October 19, 2005
Plugging Completed: October 25, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	268'	8-5/8"	268'	0'
	Production	0'	4647'	4-1/2"	4647'	2161.66'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Had cellar and pits dug out. Spotted casing jacks over well. Had Bullseye come out with 80 bbls. water. Sand bottom - 4 sacks cement at 4330'.
Pulled slips out of head. Worked casing-got 15" stretch. Trip in hole with knife. Made first cut at 300'-worked casing. Came up to 2500'-worked casing.
Trip in hole with knife-cut casing at 2000' - pulled out of hole with 25 joints of 4-1/2" casing. Pulled casing up to 830'. Cemented with 10 sacks of gel and 50 sacks cement. Pulled up to 300'-cemented with 50 sacks cement. Pulled to 40'-cemented to surface. Tallied casing: 2161.66' pipe. Rigged down-moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901
Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: Deutsch Oil Company
State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 28th day of October, 20 05

Karen J. Mitchell My Commission Expires: 4/13/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm