

RECEIVED

NOV 02 2005

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

Lease Operator: Deutsch Oil Company

Address: 107 N. Market, Suite 1115

Phone: (316) 267-7551 Operator License #: 3180

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: October 19, 2005 (Date)

by: Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: 3979' Bottom: 4440' T.D. 4710'

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 151-21,342 - 00 - 01

Lease Name: Eads

Well Number: #1-22

Spot Location (QQQQ): _____ - C - SW - SE

660' Feet from North / South Section Line

1980' Feet from East / West Section Line

Sec. 22 Twp. 29 S. R. 14 East West

County: Pratt

Date Well Completed: 7/18/88

Plugging Commenced: October 25, 2005

Plugging Completed: October 27, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	864'	8-5/8"	864'	0'
	Production	0'	4703'	4-1/2"	4703'	2423.59'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Set jacks over well. Rigid up Log-Tech. Set cast iron plug in 4-1/2" casing at 3900' with 2 sacks of cement. Pulled slips out of head.

Pulled stretch into casing. Pipe was free. Pulled out 4 joints of pipe - well kicked off. Got water truck out to kill well. Pulled casing out of well.

Had 2423.59' of 4-1/2" casing. Riggged over for tubing. Ran 30 joints of 2-3/8" tubing into well (900'). Tallied casing. Cemented well with 10 sacks of gel and 50 sacks cement. Pulled to 40' - cemented to surface. Pulled rest of tubing - loaded up casing jacks - rigged down and moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901


Address: P.O. Box 231, Claflin, Kansas 67525


Name of Party Responsible for Plugging Fees: Deutsch Oil Company

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

 KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt Expires 4/13/06



P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 28th day of October, 20 05


Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

