

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-21,805

LEASE NAME City of Stockton

WELL NUMBER #1-19

SPOT LOCATION NE NW NW

SEC. 19 TWP. 7 RGE. 17 (E) of (NW)

COUNTY Rooks

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-4-84

Plugging Completed 9-12-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR G. N. Rupe, ETAL

ADDRESS Box 2273, Wichita, Ks. 67201

PHONE # (286-5553) OPERATORS LICENSE NO. 5047

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1253'	None
				5-1/2"	3373'	2,353.72'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 3245' and 5 sacks cement Dumped sand to 3050' and 5 sacks cement. Shot casing at 2400'. Pulled 59 joints of 5-1/2" casing. Squeezed well with 2 sacks hulls, 20 sacks gel and 200 sacks 50/50 pozmix cement with 8% added gel and 3% calcium chloride.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

9-19-84

SEP 19 1984

James W. Rockhold

(employee of operator) of

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1984

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman  
Notary Public