

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: (Oil) Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR C. C. & S. Oil Operations, Inc.

ADDRESS 12 Northridge Plaza
Hays, Ks. 67601

**CONTACT PERSON Dan Schippers
PHONE (913) 628-3284

PURCHASER CRA, Inc.

ADDRESS P. O. Box 7305
Kansas City, Mo. 64116

DRILLING Lawbanco Drilling
CONTRACTOR ADDRESS P. O. Box 289
Natoma, Ks. 67651

PLUGGING
CONTRACTOR ADDRESS

TOTAL DEPTH 3325' PBD

SPUD DATE 5/11/82 DATE COMPLETED 5/19/82

ELEV: GR 1741' DF 1744' KB 1746'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 1176' DV Tool Used? NO

API NO. 15-163-21,684 00-00

COUNTY Rooks

FIELD Riffe

PROD. FORMATION Arbuckle

LEASE Hutton 'A'

WELL NO. 2


WELL LOCATION NE NE SW

Ft. from Line and

Ft. from Line of

the SEC. 19 TWP. 7 RGE. 17

WELL PLAT



KCC
KGS
(Office Use)

AFFIDAVIT

STATE OF Kansas, COUNTY OF Ellis ss, I,

Daniel F. Schippers OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Controller (FOR)(OF) C. C. & S. Oil Operations, Inc.

OPERATOR OF THE Hutton 'A' LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 2 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 12th DAY OF June, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH

SUBSCRIBED AND SWORN BEFORE ME THIS 21st DAY OF June, 19 82.

(S) Daniel F. Schippers

Robin K. McDowell

NOTARY PUBLIC, Robin K. McDowell

MY COMMISSION EXPIRES: 8-11-85

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

RECEIVED
CORPORATION COMMISSION
JUN 23 1982
10-23-82
CONSERVATION DIV
Wichita, Kansas

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1168'			
Base Anhydrite	1205'			
Topeka	2680'			
Queen Hill Sh.	2835'			
Heebner	2891			
Toronto	2912			
Lansing- K.C.	2933			
Base- K.C.	3161			
Marmaton SD	none			
Marmaton Lm.	3197			
Arbuckle	3224			
T.D.	3325			

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** New or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	17 1/2"	13 3/8"	48	89'	Common	120	3% cc 2% gel
Surface	12 1/4"	8 5/8"	23	1176'	Common	450	3% cc 2% gel
Production	7 7/8"	5 1/2"	14	3322'	ASC	150	ASC

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
4	Jet	3252-56

TUBING RECORD

Size	Setting depth	Packer set at
2 7/8"	3254.21	----

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal. Mud Acid	3252.56

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
6/12/82	pumping	23

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	40 bbls.	--- MCF	0 %	0 bbls. --- CFPS

Disposition of gas (vented, used on lease or sold)

Perforations