

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-163-23,182 -00-00

LEASE NAME WESTAR (B-4)

WELL NUMBER 1

4290 Ft. from S Section Line

1650 Ft. from E/ Section Line

SEC. 13 TWP. 7 RGE. 18 (or (W))

COUNTY ROOKS

Date Well Completed 11/15/91

Plugging Commenced 1/14/98

Plugging Completed 1/14/98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

LEASE OPERATOR CASTELLI EXPLORATION, INC.

ADDRESS 9500 WESTGATE DRIVE, SUI OKLAHOMA CITY, OK 73162

PHONE# (405) 722-5511 OPERATORS LICENSE NO. 31021

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/27/97 (date)

by HERB DEINES (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation ARBUCKLE Depth to Top 3400 Bottom 3405 T.D. 3405

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
ARBUCKLE	OIL	0	90	13-3/8	90	0
		0	1337	8-5/8	1337	0
		0	3401	5-1/2	3401	2091

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

SANDED BACK TO 3550' & CAPPED W/ 5 SX PULLED CSG & TOPPED OFF W/ 5 SX
1ST PLUG @ 1520' W/ 105 SX & 300# HULLS HOLE STAYED FULL. PLUGGED W/ 250 SX
2ND PLUG @ 916' W/ 40 SX 60-40 POZ W/ 10% GEL & 300# HULLS.
3RD PLUG @ 412' & CIRC 95 SX TO SURFACE STATE MAN ON LOC - RICH WILLIAMS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor EXPRESS WELL SVC., INC. / ALLIED CEMENTING CO License No. 6426


Address P.O. BOX 426 VICTORIA, KS 67671 / P.O. BOX 31 RUSSELL, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CASTELLI EXPLORATION, INC.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Thomas P. Castelli (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas P. Castelli
9500 WESTGATE DRIVE, SUITE 101
(Address) OKLAHOMA CITY, OK 73162



SUBSCRIBED AND SWORN TO before me this 21st day of January, 19 98

Diana L. Price Notary Public
Commission Expires: Feb. 10, 2001

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas
1-23-98
JAN 23 1998