

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD #4
K.A.R.-82-3-117

API NUMBER 15-163-22-195-00-00

LEASE NAME American Lariat Hale

WELL NUMBER #1 (A-6)

4950' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 13 TWP. 7S RGE. 18W (E) or (W)

COUNTY Rooks

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR 2970 Bowvalley Square IV

ADDRESS 250-6th Ave. S.W., Calgary Alberta, Canada T2P3H7

PHONE# (403) 266-1024 OPERATORS LICENSE NO. 6656

Character of Well Non-Commercial

Date Well Completed 12/5/1983

Plugging Commenced 9/27/1988

(Oil) Gas, D&A, SWD, Input, Water Supply Well

Plugging Completed 9/27/88

The plugging proposal was approved on by Shari Feist 9/12/1988 (date)

by (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Previously mailed with form CP-1

Producing Formation Arbuckle Depth to Top 3388' Bottom 3443'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
9-30-88
SEP 30 1988

Formation	Content	From	To	Size	Put in	Pulled out
Stone Corral	Anhydrite	Surf.	1328	8 5/8	1328'	None
Topeka	Chalky Limestone	Surf.	3429	5 1/2	3429'	None
Lsg. K.C.	Shale & Limestone					None
Marmaton	Cherty Sand					Wichita, Kansas
Arbuckle	Dolomite					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set Baker Cast Iron bridge Plug @ 3360' (Above arbuckle)

Filled and squeezed to 800# inside 5 1/2" casing

Filled annulus between 8 5/8 and 5 1/2 casing and squeezed to 800#

Total cement 480 Sx 60/40 Pozmix 6% Gel with 700# Cotton seed hulls

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jordan Petroleum LTD License No. 6656

Address (see above Co. operator)

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jordan Petroleum, LTD.


STATE OF Kansas COUNTY OF Rooks, ss.

Charles D. Farr (Petroleum consultant) (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Dale Balthazor K.C.C. Rep. on location.

(Signature) Charles D. Farr

(Address) 209 W. 33st Hays, Kansas 67601



BEFORE AND SWORN TO before me this 28th day of September, 19 88

Nancy Taggart Notary Public

My Commission Expires: 7-2-91

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-22,195-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR AMERICAN LARIAT INC. OPERATORS LICENSE NO. 6656
% JORDAN PETROLEUM, LTD 250-6th Ave S.W. CALGARY, ALBERTA T2P3H7, CANADA.
ADDRESS 2970 BOWVALLEY SQUARE IV. PHONE # (403) 226-1024

LEASE (FARM) HALE WELL NO. 1 WELL LOCATION C-NE-NE-NE COUNTY ROOKS
T. 13 TWP. 7S RGE. 18W (E) or (W) TOTAL DEPTH 3443' PLUG BACK TD 3404'

Back One:

Oil WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 1320' CEMENTED WITH 475 SACKS

CASING SIZE 5 1/2" SET AT 3429' CEMENTED WITH 130 SACKS

PERFORATED AT Arbuckle (3388-90, 3391-94) Lsg. K.G. (3272-78, 3254-58, 3214-16,
3152-58, 3140-42, 3062-64)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL We do not intend to re-

Will comply with recommendation in accordance with K.S.A. 55-101

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1988
9-30-88

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes _____ IS ACCOMPANIED? Yes _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Charles D. Farr PHONE # () 913-628-2513

ADDRESS 209 W. 33st. Hays, Kansas 67601

PLUGGING CONTRACTOR Allied Cementing Co. LICENSE NO. _____

ADDRESS Plainville, Kansas 67663 PHONE # () 913-434-2812

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Charles D. Farr
(Operator or Agent)

DATE: 8 September 1988