

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-20123-00-00  
LEASE NAME SHIRER / KEENER  
WELL NUMBER 2D

RECEIVED  
JUN 22 2004  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1650 Ft. from S Section Line  
660 Ft. from E Section Line  
SEC. 9 TWP. 18 RGE. 14 (E) or (W)

LEASE OPERATOR MAD DOG OIL  
ADDRESS 862 NW 70 th AVE OLMITZ, KS 67564

COUNTY BARTON  
Date Well Completed 10-26-67  
Plugging Commenced 2-24-04  
Plugging Completed 2-24-04

PHONE# (620) 653-4563 OPERATORS LICENSE NO. 32012

Character of Well OIL  
Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-23-04 (date)  
by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation TOPEKA/LAN/ARB Depth to Top 3066 Bottom 3480 T.D. 3480

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To   | Size  | Put In | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| TOPEKA    | OIL     | 3066 | 3087 | 5 1/2 |        | NONE       |
| LANING/KC | OIL     | 3203 | 3347 | 5 1/2 |        | NONE       |
| ARBUCKEL  | oil     | 3427 | 3430 | 5 1/2 |        | NONE       |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
275sk 60/40 poz common 1896 lbs cmt gel 300 lbs cotton seed balls  
mix 25 skcmt down braden head tubing shot off @1600ft +/- EST circ W/H2o  
good circ mix 125 sk cmt good circ no cmt pull tubing to 800 ft EST circ  
mix 60sk cmt circ cmt to surface pull tubing out & rig up to 5 1/2 casing  
mix 65sk cmt w/hulls shut down & flush max psi 300lbs isip 150#

Name of Plugging Contractor SERVICES ACID LLC Klima Well Service License No. 7023  
Address PRATT, KS, 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MAD DOG OIL CO

STATE OF KS COUNTY OF BARTON, ss.

JOHN MADDOX

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Maddox

(Address) 862 NW 70th AVE Olmitz, KS

SUBSCRIBED AND SWORN TO before me this 18th day of June, 2004

Patricia Collins  
Notary Public

My Commission Expires: Aug 6, 2004

PATRICIA COLLINS  
Notary Public - State of Kansas  
My Appt. Expires Aug 6, 2004

Form CP-4  
Revised 05-88