

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

NOV 09 2005

KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: C & K Oil Company

Address: P.O. Box 531, Claflin, Ks. 67525

Phone: (620) 587-0150 Operator License #: 31561

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: October 14, 2005 - Emergency (Date)

by: Pat Staab (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Open Hole-Arbuckle Depth to Top: \_\_\_\_\_ Bottom: 3285' T.D. 3288'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - N/A 009-19083-00-00

Lease Name: Hertach

Well Number: #6

Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - SE

2310' Feet from  North /  South Section Line

2310' Feet from  East /  West Section Line

Sec. 12 Twp. 18 S. R. 11  East  West

County: Barton

Date Well Completed: Spud: 12/19/1952

Plugging Commenced: October 14, 2005

Plugging Completed: November 2, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	247'	8-5/8"	247'	0'
	Production	0'	3285'	5-1/2"	3285'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Worked on well to put into production but just couldn't get it - set up to plug. Ran 1817' of tubing (out of derrick) - open-ended. Had cellar dug out. Put rubber in head - got ready to plug well. Backhoe dug down to surface pipe so Scotts Welding could cut a hole and weld a collar on surface pipe - to circulate out of. Allied hooked up to tubing-pumped 300 sacks of cement-500# hulls. Pulled up to 1000'-pumped in 25 more sacks cement and hulls. Squeezed 40 more sacks down backside-stayed full. Finished pulling tubing-laying down. Broke workover head off well, cleaned up, rigged down and moved off.


Name of Plugging Contractor: D. S. & W. Well Servicing, Inc License #: 6901

Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: C & K Oil Company

State of Kansas County, Barton, ss.

Edward Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

  
KAREN J. MITCHELL  
Notary Public - State of Kansas  
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich  
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 8th day of November, 20 05

Karen J. Mitchell  
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Sm*