

State Conservation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

15-065-02801-00.00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm.Div.
office within 30 days

API Number Drld 1657
LEASE NAME Brush Creek Unit
WELL NUMBER 105
330-2970 Ft. From S. Section
Line
3300 Ft From E. Section
Line
SEC 4 TWP. 9 RNG 23W
COUNTY Graham
Date Well Completed
6/7/57
Plugging Commenced
.11/1/05.....
Plugging Completed
11/1/05

KCC
BEM
11-14-05
RBDMS
CP1, CP 2/3

OPERATOR: John J. Darrah, Jr.
ADDRESS: 225 N. Market, #300, Wichita, KS 67220
PHONE# (316) 26-2243 OPERATORS LICENSE NO: 5088~
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/1/05
by Pat Staab

KCC District Agent's Name

Is ACO-1 Filed? _____ If not, is well log attached? filed w/ Plug App
Producing formation Lansing Depth to Top 3672 Bottom 3817 T.D. 3838
Show depth and thickness to all water, oil and gas formations

OIL, GAS OR WATER RECORDS		I		CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled OUT
<u>Lansing</u>	<u>Oil & Water</u>	<u>3672</u>	<u>3817</u>	<u>8 5/8</u>	<u>197</u>	<u>0</u>
<u>Topeka</u>	<u>Water</u>	<u>3204</u>	<u>3490</u>	<u>5 1/2</u>	<u>3838</u>	<u>0</u>
				<u>2 3/8</u>	<u>3194</u>	<u>2200</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, if cement or other plugs were used, state the character of same and depth placed, from ft to feet each set.

CIBP @ 3500, Plugging perfs @ 1970 & 1160; tubing to 2775, displaced 40sx 60-40 w/10% gel + 300# hulls, tubing to 200'0', circulated to surface with 90 sks cement as above +200# hulls, pull tubing, 40 sx AA down 5 1/2 to 400 psi, pumped 50 sx AA down 8 5/8 x 5 1/2 annulus to 200 psi.

Name of plugging contractor Swift Services TR Services + Rental, Inc License No. 33346
Address PO Box 466, Ness City, KS 67560 271 Lake Rd Pratt, KS 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah, Jr.

KCC
BEM
11-14-05
RBDMS
CP1, CP 2/3

STATE OF Kansas COUNTY OF Sedgwick, ss.


G>P> Stoeppelwerth, Agent of above-described well, first being duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

225 N. Market #300, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 11th day of November, 2005

Patricia C Byerlee
Notary Public



My Commission Expires: 9/9/2006 - 12/11/2005

RECEIVED
NOV 14 2005
KCC WICHITA

BEM