

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
K.A.R. -82-3-117

API NUMBER 15-041-20-092-00-00  
LEASE NAME Arvin Eilders  
WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

995  
990 Ft. from South Line of Section  
1650 Ft. from East Line of Section  
1759  
KCC  
Bem. 05  
11-7-05  
Per Dist II  
RBD/ms  
GPS

LEASE OPERATOR American Energies Corporation SPOT LOCATION NE SW SE  
ADDRESS 155 N Market, Suite 710 Section 29 Township 14 Range 1E  
CITY, STATE, ZIP Wichita, KS 67202 County Dickinson  
PHONE # 316-263-5785 Date Well Completed 5/3/84  
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Commenced 8/30/2005  
Date Plugging Completed 9/1/05 (date)  
The plugging proposal was approved on 9/1/05  
by State Plugging Agent - Greg Eves (KCC District Agent's Name)  
Is ACO-1 Filed? Yes If not, is well log attached?  
Producing Formation(s) Burg Sand Depth to Top 2536 Bottom 2550 T.D. 2586  
Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

| FORMATION  | CONTENT     | FROM    | TO    | SIZE       | PUT IN | PULL OUT |
|------------|-------------|---------|-------|------------|--------|----------|
| Surface    | Water sands | 205'    | 0'    | 8 5/8" 23# | 205'   | None     |
| Production | Oil         | Surface | 2586' | 4 1/2"     | 2586'  | 1600'    |
|            |             |         |       |            |        |          |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.


- 8/30/05 - Pulled out rods and tubing. Sanded bottom with 100 gallons sand.
- 8/31/05 - Spotted cement on botton. Set up jacks. Pulled out slips and got ripper ready.
- 9/1/05 - Ripped pipe and pulled out 51 jts of 4 1/2" casing. Cut pipe at 1600'.
- Ran 2" tubing 260' - pumped cement to surface. Job Complete.

Name of Plugging Contractor American Energies Corporation  
Licence No. 5399  
Address 155 N. Market #710 City: Wichita State: Kansas Zip 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation (Operator)


STATE OF KANSAS COUNTY OF Sedgwick, ss.


Alan L. DeGood, President (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature)   
(Alan L. DeGood, President, American Energies Corporation)

(Address) 155 North Market, Suite 710 City: Wichita State: Kansas Zip 67202

SUBSCRIBED AND SWORN TO me this \_\_\_\_\_ day of \_\_\_\_\_ 2004



  
Melinda S. Wooten, Notary Public

My Commission Expires: 3/12/08

Form CP-4  
Revised 12-92

RECEIVED  
NOV 04 2005  
KCC WICHITA  
Bur

