

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation
Address: 8080 East Central, Suite #300, Wichita, Ks. 67230
Phone: (316) 636-2737 Operator License #: 5003

API Number: 15 - 047-21,456-00-00
Lease Name: BIAGGI "A"
Well Number: #1-28

Type of Well: oil & gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): _____ - SE - SW - SE
3630 ³³⁰ Feet from North / South Section Line
1650 Feet from East / West Section Line

The plugging proposal was approved on: 10/18/05 (Date)
by: Steve Durant (KCC District Agent's Name)

Sec. 28 Twp. 25 S. R. 20 East West
County: Edwards

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4710 Bottom: 4722 T.D. 4810
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Date Well Completed: 11/13/01
Plugging Commenced: 10/18/05
Plugging Completed: 10/19/05

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | | | | 8-5/8" | 323 | 0 |
| | | | | 4-1/2" | 4805 | 2820' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole, sand was at 4660', dumped 4 sacks cement, had 26" stretch, ripped casing at 3240', 3020', 2820' came free, pulled up to 1300', pumped 12 gel and 50 sacks, pulled to 650', pumped 80 sacks, pulled to 330', pumped 40 sacks, pulled to 40', pumped 10 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 401 West Main, Lyons, Kansas 67554

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel

(Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, Kansas 67206

SUBSCRIBED and SWORN TO before me this 2nd day of November 20 05

Melinda K. Valadez My Commission Expires 2/1/2007
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 04 2005
KCC WICHITA

see
BEM
11-7-05
KCDMS
CP2/3
Dist I

KCC
BEM
11-7-05
CP2/3
RCDMS
Dist I