

RECEIVED

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

OCT 31 2005

Form CP-1  
September 2003

WELL PLUGGING APPLICATION KCC WICHITA

Please TYPE Form and File ONE Copy

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 167-20,371-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 10/23/69

Well Operator: R.P. Nixon Oper., Inc. KCC License #: 5252  
(Owner / Company Name) (Operator's)

Address: 207 West 12th City: Hays

State: KS Zip Code: 67601 Contact Phone: ( 785 ) 628 - 3834

Lease: Heinze Well #: 4 Sec. 24 Twp. 15S S. R. 12 ☐ East ☒ West

- W/2 - SE - SE Spot Location / QQQQ County: Russell

660 Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☒ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well

☐ SWD Docket # ☐ ENHR Docket # ☐ Other:

Conductor Casing Size: none Set at: Cemented with: Sacks

Surface Casing Size: 8 5/8" Set at: 313' Cemented with: 200 Sacks

Production Casing Size: 5 1/2" Set at: 3323' Cemented with: unknown - 100 ? Sacks

List (ALL) Perforations and Bridgeplug Sets: 3190-96' 3170-75' 3100-04' 3085-87' 3071-73' 3035-41' 2724-28' 2845-47'

2839-41' 2829-31' 2819-21' Plug set at 2650' and stuck in hole below collapsed casing.

Elevation: 1863 (☐ G.L. / ☒ K.B.) T.D.: 3331' PBTD: Anhydrite Depth: 753' (top)  
(Stone Corral Formation)

Condition of Well: ☐ Good ☐ Poor ☒ Casing Leak ☒ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Lok-set plug in hole at 2650'. Holes in casing from 250-530'  
and when trying to drill out cement, got out of the casing at 522'. Casing collapsed. Would like to tie on to casing and pump cement  
amount recommended by KCC to get circulation to surface.

Is Well Log attached to this application as required? ☐ Yes ☒ No Is ACO-1 filed? ☐ Yes ☒ No

If not explain why? Bought lease from Ray Mader and did not receive these records.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dan A. Nixon

Phone: ( 785 ) 628 - 3834

Address: 207 West 12th City / State: Hays, KS 67601

Plugging Contractor: Allied Cementing KCC License #: 99996  
(Company Name) (Contractor's)

Address: Box 31 Russell, KS 67665 Phone: ( 785 ) 483 - 2627

Proposed Date and Hour of Plugging (if known?): as soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10.28.05 Authorized Operator / Agent: [Signature]  
(Signature)

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 31 2005  
KCC WICHITA

RAY MADER 24-15-12W  
RUSSELL, KS. #4 HEINZE APP W/2 SE SE  
Contr. SHIELDS DRLG. COMPANY Cty. RUSSELL  
Geol. R. P. NIXON Pool DRISCOLL  
E. 1863 KB Cm. 10/23/69 Cp. 11/26/69 IP PMP 35 BOPD/ARB  
3323-31  
API 15-167-20,371



| LOG Tops       | Depth | Datum | Csg. 8-5/8" 313/200 sx             |
|----------------|-------|-------|------------------------------------|
| *ANH           | 753   | +1110 | 5 1/2" 3323                        |
| TOP            | 2616  | - 753 |                                    |
| HEEB           | 2904  | -1041 | DST 3035-95/1', 180' GIP, 305'     |
| TOP            | 2922  | -1059 | GSY OCM, BHP 1480-1320#/30"        |
| BR LM          | 2993  | -1130 | FP 178-190#                        |
| LANS           | 3004  | -1141 | DST 3165-3215/1', 10' V SL OIL SP  |
| CONG           | 3272  | -1409 | M, IBHP 90#/30", ALL OTHER         |
| ARB            | 3318  | -1455 | PRESS 0#                           |
| RTD            | 3331  | -1468 |                                    |
|                |       |       | CO TO 3331 TD, 55 GALS ACID, FU    |
|                |       |       | 1800' OIL/2 HRS, 750 ACID, SWB LD, |
|                |       |       | NO TST, POP                        |
|                |       |       | NO CORES                           |
| *DRILLER'S TOP |       |       |                                    |

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Nixon, R P Operations, Inc  
207 W 12th  
Hays, KS 67601-3810

November 07, 2005

Re: HEINZE #4  
API 15-167-20371-00-00  
W2SESE 24-15S-12W, 660 FSL 990 FEL  
RUSSELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,



David P. Williams  
Production Supervisor

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550