

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

RECEIVED

OCT 31 2005

KCC WICHITA

Form CP-1
September 2003

This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 167-21,533-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 12/27/80

Well Operator: R.P. Nixon Oper., Inc. KCC License #: 5252
(Owner / Company Name) (Operator's)

Address: 207 West 12th City: Hays

State: KS Zip Code: 67601 Contact Phone: (785) 628 - 3834

Lease: Heinze Well #: 7 Sec. 24 Twp. 15S S. R. 12 East West

- NW - SW - SE Spot Location / QQQQ County: Russell

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: none Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 212' Cemented with: 150 Sacks

Production Casing Size: 4 1/2" Set at: 3348' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3310-20' 3305-10' 3296-99' 3193-96' 3167-69' 3103-05' 3088-90' 3039-41'
3012-14' 2929-32' 2868-70' 2742-44' 2732-34'

Elevation: 1852 (G.L. / K.B.) T.D.: 3350' PBTD: _____ Anhydrite Depth: 739-67'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): casing leak, got drilling mud when pulling tubing from well.
Would like to tie on to casing and pump KCC recommended amount of cement.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? too old

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dan A. Nixon

Phone: (785) 628 - 3834

Address: 207 West 12th City / State: Hays, KS 67601

Plugging Contractor: Allied Cementing KCC License #: 99996
(Company Name) (Contractor's)

Address: Box 31 Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): as soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10.28.05 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

4/06

replacement card

R & H OIL & GAS CO
RUSSELL KS

24-15S-12W
NW SW SE

#7 HEINZE

site: 6 N & 3-1/2 E OF BEAVER KS
contr: BERGMAN DRILLING

cty: RUSSELL
field: DRISCOLL

API 15-167-21533

fr	spc	drig	card	last
date 09/09/80	date 12/27/80	comp 01/02/81	issued 11/12/81	revised 06/09/97

ELV: 1850 TOPO
 tops.....depth/ datum
 RTD.....3350 -1500
 NO TOPS RPTD

IP status:
OIL, P 7 BOPD, ARB 3310-3320, 10/01/81
 INFO RELEASED: 6/9/97 - WAS OIL WELL - TEMP
 COMP
 CSG: 8-5/8" 212 / 150 SX, 4-1/2" 3348 / 200 SX
 NO CORES OR DSTS
 MICT - CO, PF (ARB) 3310-3320 (EST), AC'D, SO, POP,
 IPP 7 TO 8 BOPD, 10/1/81 - NO OTHER INFO RELEASED
 BY OPERATOR OR ON KCC RECORDS; ALL REQUESTS
 FOR INFO DENIED

COPYRIGHT 1997
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

RECEIVED
 OCT 31 2005
 KCC WICHITA

BERGMAN DRILLING, INC.

DRILLERS LOG

RECEIVED

DEC 31 2005


KCC WICHITA

Re: Heinze# 7
NE SW SE Section 24-15S-12W
Russell County, Kansas


OPERATOR: R & H Oil & Gas Company
CONTRACTOR: Bergman Drilling, Inc.
COMMENCED: December 27, 1980
COMPLETED: January 4, 1981
TOTAL DEPTH: 3350' Set 212' 8 5/8" w/150 sacks


0	215	Post Rock
215	638	Shale & Red Bed
638	920	Red Bed & Shale
920	1475	Shale
1475	1760	Lime & Shale
1760	1915	Shale & Lime
1915	1995	Shale
1995	2425	Lime & Shale
2425	2665	Shale & Lime
2665	2777	Shale
2777	2895	Lime & Shale
2895	3025	Lime & Shale
3025	3110	Shale
3110	3167	Lime & Shale
3167	3209	Lime & Shale
3209	3280	Lime
3280	3345	Lime & Sand w/ Delomite
3345	3350	Sand & Lime
3350		RTD Set 4 1/2" @ 3348 1/2 w/200 sx.

We certify that the above and foregoing to be true and correct copy of the drillers log on the # 7 Heinze, located in Russell County, Kansas as revealed by the records of Bergman Drilling, Inc.


Harold I. Bergman

Subscribed and sworn to before me this 5th day of January, 1981.


Alma A. Neises, Notary Public
My commission expires May 31, 1982



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Nixon, R P Operations, Inc
207 W 12th
Hays, KS 67601-3810

November 07, 2005

Re: HEINZE #7
API 15-167-21533-00-00
NWSWE 24-15S-12W, 990 FSL 2310 FEL
RUSSELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



David P. Williams
Production Supervisor