

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

Rev. 12/14/82  
FORM CP-1

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1983  
11-10-83  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
File One Copy

API NUMBER 15-163-22,193-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR H.K. & W. Oil OPERATORS LICENSE NO. 6280

ADDRESS RFD 1 Great Bend, KS 67530 PHONE # (316) 793-7327

LEASE (FARM NAME) Bigge WELL NO. 1

WELL LOCATION SW NE SW SEC. 11 TWP. 7 RGE. 18 ~~XX~~ or (W)

COUNTY Rooks TOTAL DEPTH 3514' FIELD NAME \_\_\_\_\_

check one:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A X

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? operator to be filed by  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11-1-83 10:20

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leonard Williamson ADDRESS Box 823 Great Bend, KS 67530

PHONE # (316) 793-8366

PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE NO. 5929

ADDRESS Box 823 Great Bend, KS 67530 PHONE # (316) 793-8366

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME H.K. & W. Oil

ADDRESS RFD 1 Great Bend, KS 67530 PHONE # (316) 793-7327

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OR ACTING AGENT.

SIGNED: Leonard Williamson  
(Applicant or Acting Agent)

DATE: 11-1-83

15-163-22193-00-00

DRILLER'S WELL LOG

DATE COMMENCED: October 26, 1983  
DATE COMPLETED: November 1, 1983

H.K. & W. Oil  
BIGGE #1  
SW NE SW  
Sec. 11, T7S, R18W  
Rooks County, Ks.

ELEVATION: 1899 K.B.

0 - 1373' Surface Soil, Sand, Red Bed  
1373 - 1410' anhydrite  
1410 - 2818' Shale, Shells, Lime strk.  
2818 - 2844' Lime  
2844 - 2860' Shale & Sand  
2860 - 3075' Lime  
3075 - 3079' Shale  
3079 - 3101' Lime & Shale  
3101 - 3339' Lime  
3339 - 3467' Shale, Lime, Chert, Sand  
3467 - 3514' Dolomite  
3514' RTD

FORMATION DATA

Anhydrite 1373'  
Howard 2818'  
Severy 2844'  
Topeka 2860'  
Heebner 3075'  
Toronto 3101'  
Kansas City 3119'  
Base K.C. 3339'  
Conglomerate 3388'  
Arbuckle 3467'  
RTD 3514'

Surface Pipe: Set new 8-5/8"  
24# pipe @ 1377' w/250 sacks Howco  
Lite & 200 sacks 50/50 pozmix 2%  
gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 1st day of November 1983.

My Comm. Expires:

4-29-86

Quincy M. Hague  
Notary Public

ECI  
STATE OF KANSAS

NOV 10 1983

Wichita, Kansas