

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

Rev. 12/14/82  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API NUMBER 15-163-22,285-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR National Development Co. OPERATORS LICENSE NO. 5114

ADDRESS 833 North Waco Wichita, KS 67203 PHONE # (316) 267-1331

LEASE (FARM NAME) Reed WELL NO. 1

WELL LOCATION C E/2 W/2 NE SEC. 1 TWP. 7 RGE. 18 ~~(E)~~ or (W)

COUNTY Rooks TOTAL DEPTH 3413 FIELD NAME \_\_\_\_\_

check one:  
OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_ X

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? to be filed by operator  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3:00 a.m. 2-4-84

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Draney ADDRESS Box 823 Great Bend, KS 67530

PHONE # (316) 793-8366

PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE NO. 5929

ADDRESS Box 823 Great Bend, KS 67530 PHONE # (316) 793-8366

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME National Development Co.

ADDRESS 833 North Waco Wichita, KS 67203 PHONE # (316) 267-1331

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OR ACTING AGENT.

RECEIVED  
STATE CORPORATION COMMISSION

SIGNED: Bill Draney  
(Applicant or Acting Agent)

FEB 10 1984

DATE: 2-4-84

CONSERVATION DIVISION  
Wichita, Kansas 2-10-84

15-163-22285-00-00

DRILLER'S WELL LOG

DATE COMMENCED: January 29, 1984  
DATE COMPLETED: February 4, 1984

National Development Co.  
REED #1  
C E/2 W/2 NE  
Sec. 1, T7S, R18W  
Rocks County, Ks.

ELEVATION: 1907 K.B.

0 - 447' Surface Soil, Post Rock, Shale  
447 - 1048' Sand  
1048 - 1349' Red Bed  
1349 - 1380' Anhydrite  
1380 - 2827' Lime & Shale  
2827 - 3035' Lime  
3035 - 3039' Shale  
3039 - 3063' Lime & Shale  
3063 - 3310' Lime  
3310 - 3408' Shale & Lime  
3408 - 3413' Dolomite  
3413' RTD

FORMATION DATA

Dakota Sand 447'  
Cedar Hills 838'  
Anhydrite 1349'  
Topeka 2827'  
Heebner 3035'  
Toronto 3063'  
Lansing K.C. 3082'  
Base K.C. 3310'  
Arbuckle 3408'  
RTD 3413'

Surface Pipe: Set new 8-5/8"  
20# pipe @300' w/170 sacks  
60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 8<sup>th</sup> day of February 1984.

My Comm. Expires:

4-29-86

Alveth M. Hoque  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 10 1984  
CONSERVATION DIVISION  
Wichita, Kansas