

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW-SW-NE, SEC. 8, T 7 S, R 18 W E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22, 107-00-00

TECHNICIAN'S PLUGGING REPORT

2310 FEET FROM N/S SECTION LINE

2310 FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 6111

LEASE NAME BOUCHEY WELL # 1

OPERATOR: EMPHASIS OIL OPERATIONS  
NAME & ADDRESS SUBSIDIARY OF N.B. COMPANY  
P.O. BOX 506 INC.  
RUSSELL, KANS.  
67665-0506

COUNTY ROCK  
WELL TOTAL DEPTH 3470 FEET \$ 112.78  
CONDUCTOR PIPE: SIZE 0 FEET  
SURFACE CASING: SIZE 8 5/8 FEET 253

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR EMPHASIS OIL OPERATIONS LICENSE NUMBER 622 TAG.

ADDRESS P.O. BOX 506 RUSSELL, KANS. 67665

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 5<sup>th</sup> MONTH: AUG. YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM RON BURTON

(COMPANY NAME) EMPHASIS OIL OPERATIONS (PHONE) 913-483-5345

WERE: 8 5/8" - 253<sup>ft</sup> SP. OIL 1/160<sup>st</sup> COMMON - 2% GEL - 3% CA-CL. (BY ALLIED)  
ORDER 200<sup>st</sup> 50/50 FORMIX 6% GEL - 3% CA-CL. AND 8 5/8" PLUG  
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS  
ELV. 1906 - ANNY 1376 - ARBUCKLE 2425'

PLUGGING PROPOSAL RECEIVED BY [Signature] (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE X

OPERATIONS COMPLETED: HOUR: AUG DAY: 5<sup>th</sup> MONTH: 1:00 PM YEAR: 19 83

ACTUAL PLUGGING REPORT

ORDERED 200<sup>st</sup> 50/50 FORMIX 6% GEL - 3% CA-CL. AND 8 5/8" PLUG  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS  
1<sup>st</sup> PLUG @ 3390 FT 1/20<sup>st</sup> OMT, 2<sup>nd</sup> PLUG @ 1380 FT 1/20<sup>st</sup> OMT.  
3<sup>rd</sup> PLUG @ 480 FT 1/100<sup>st</sup> OMT, 4<sup>th</sup> PLUG @ 240 FT 1/40<sup>st</sup> OMT.  
5<sup>th</sup> PLUG <sup>SAND BRIDGE</sup> HULLS - PLUG @ 40 FT 1/10<sup>st</sup> OMT. (10<sup>st</sup> OMT. RAT HOLE (CIRCULAR))

REMARKS: CEMENTED BY ALLIED OMT.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1983

8-17-83

CONSERVATION DIVISION  
Wichita, Kansas

I (~~DO~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) DOIC

INVOICED

DATE 8-18-83

INV. NO. 5250-W

FORM CP-213  
REV. 6-83