

6 010756

6-4

API NUMBER 15- 15-163 22236 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW ^{SE} SW SE, SEC. 13, T 7 S, R 18 W/E
290 feet from S section line
910 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3662

Lease Name Miller Well # 1

Operator: Arroyo Pet.

County Rooks 108.87

Name & Address 520 S. Holland

Well Total Depth 3350 PB 3340 feet

Wichita, Kansas

Conductor Pipe: Size 13 3/8 feet 89

Surface Casing: Size 8 5/8 feet 1235

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Arroyo License Number 3662

Address 520 S. Holland
Wichita, Kansas

Company to plug at: Hour: 8:30 A.M. Day: 4 Month: 6 Year: 19 91

Plugging proposal received from Mike Savier

(company name) Arroyo Pet. (phone)

were: Order 300 sx. cement. 65/35 pox mix. 8% gel. and 300# hulls. Run wire line to T.D., Tie onto 8 5/8 and pressure up; tie onto casing and pump down cement, 5 1/2 casing @ 3340. Top Dakota 560 - 1450 - Elev. 1791'. 8 5/8 - 5 1/2 annulus was cemented w/225 sx. cement.

Plugging Proposal Received by Dale F. Balthazor

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 A.M. Day: 4 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Ran wire line to 3304 - pumped down 8 5/8 locked @ 1000#. Pumped down 5 1/2 casing - 300 sx. cement and 300# Hulls. Max. pressure 1100#.

closed w/500#.

RECEIVED
STATE CORPORATION COMMISSION

6-13-91
JUN 13 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cement Company (Gary)

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE 6-20-91

INV. NO. 32192

6-4 AUG 12 1991

Signed Dale F. Balthazor
(TECHNICIAN)