

6 010637

9-27

403

API NUMBER 15-

163-22, 195-00-00R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE NE, SEC. 13, T 7 S, R 18 W/E

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6656

Lease Name Hale Well # 1

Operator: American Lariat, Inc.  
Name & ~~Jordan Pet LTD~~

County \_\_\_\_\_ Rooks 111.90

Address 2970 Bow Valley Sq.

Well Total Depth 3443 feet

Calvary Alberta, Canada

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1320

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Jordan Pet License Number 6656

Address Same

Company to plug at: Hour: \_\_\_\_\_ Day: 27 Month: Sept Year: 19 88

Plugging proposal received from Charles D. Farr

(company name) Same (phone) \_\_\_\_\_

were: Order 400 sks cement 60/40 Poz 6% Gel 600# Hulls. Ordered 200 sks cement 60/

40 Poz 8% Gel 400# Hulls. 5 1/2" casing at 3429'. Cast iron plug at 3361'. Perf 3214' - 78'.

Anhydrite 1311' Elev. 1858' S.L.D. 1400' Top 458'

RECEIVED  
STATE CORPORATION COMMISSION

11-8-88

NOV 8 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by D.F.B.

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 27 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Pumped down 8 5/8" 90 sks cement w/150# Hulls, 500# press and rup-  
tured csg. Circ out of csg. Pumped down 5 1/2" casing 310 sks w/350# Hulls. Max press 200#

closed w/0#. Pumped down csg. Circ in annulus, pumped down csg 80 sks cement w/200# Hulls.

Max 1400#. Closed w/800#.

Remarks: Allied Cement Co.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

DATE 11-9-88

Signed Dale F. Balthazor  
(TECHNICIAN)

Dale F. Balthazor

INV. NO. 22956