

6 040898

6-7-88

203
K

API NUMBER 15-163-22132-00-00

SE SW NE SEC. 13, T 7 S, R 18 W/

2303 feet from N S section line

1713 feet from E section line

Lease Name City of Stockton Well # 7-13

County Rooks 110.99

Well Total Depth 3415 feet

Conductor Pipe: Size 13 3/8 feet 118' w/100

Surface Casing: Size 8 5/8 feet 1323 2/450

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8098

Operator: Damson Oil Inc.

Name & Address 3300 No. A

Building 8

Midland, Texas 79705

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks.

Company to plug at: Hour: 8:30AM Day: 7 Month: June Year: 19 88

Plugging proposal received from Fred Simondi

(company name) Damson (phone) _____

were: 5 1/2" casing set at 3414' w/155 sks cement. Perfs at 3367' to 3381'.

Ordered 300 sks 65/35 Poz 10% Gel plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15PM Day: 7 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 140 sks cement plus 5 sks Hulls mixed in cement. (90 bbls slurry) Max Psi 1500#. Shut in 1000#. Pumped in 8 5/8" casing 130 sks cement

(60 bbls slurry) Max Psi 1400#. Shut in 750#.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1988

7-6-88

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
do not observe this plugging.

DATE 7-12-88

INV. NO. 21272
6-7

Signed Dennis L. Hamel
Dennis Hamel (TECHNICIAN)

SEP 12 1988 NOV 16 1988