

6 030964

10-2-87
API NUMBER 15-163-21967-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW NE , SEC. 13 , T 7 S, R 18 W/E

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5900

Lease Name Conn (A-4) Well # 1-B 7-13

Operator: Lawbanco Drilling Inc.
Name & Address
Box 289
Natoma, Kansas 67651

County Rooks 11.90
Well Total Depth 3443 feet
Conductor Pipe: Size 8 5/8 feet 234
Surface Casing: Size feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 2 Month: October Year: 19 87

Plugging proposal received from Mike Kelso

(company name) Kelso Casing (phone)

were: 8 5/8" set at 234' w/NA sx 5 1/2" set at NA w/NA sk. Perfs 3400' - 04'.
Perf at 1200' Anhy w/100 sks cwc. Order 95 sks ATL 65/35 Pozmix 10% Gel
2% Dical. Cement Blend and 130 sks 60/40 Pozmix 10% Gel 3% CC Lite Cement Blend
200# Hulls Allied Cement Co. B. and L. Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 PM Day: 2 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/200# Hulls in with 95 sks ATL Cement Blend to Anhydrite (1231) followed with 50 sks Lite Cement Blend to Max Psi 1000#. Close in Psi 1000#. Squeeze 8 5/8" annulus. Blew off head cement at surface. Plug complete.

STATE CORPORATION COMMISSION

OCT 23 1987

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-26-87
INV. NO. 18667-66

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow