

6 030964

corrected plugging report (well #)

API NUMBER 15-163-21967-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW NE, SEC. 13, T 7 S, R 18 W/E
4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5900

Lease Name Conn (2) Well ~~1-B-A-4~~

Operator: Lawbanco Drilling Inc.

County _____ Rooks

Name & Address Box 289

Well Total Depth 3443 feet

Natoma, Kansas 67651

Conductor Pipe: Size 8 5/8 feet 234

785-885-4676

Surface Casing: Size _____ feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 2 Month: October Year: 19 87

Plugging proposal received from Mike Kelso

(company name) Kelso Casing (phone) _____

were: 8 5/8" set at 234' w/NA sx 5 1/2" set at NA w/NA sk. Perfs 3400' - 04'

Perf at 1200' Anhy w/100 sks cwc. Order 95 sks ATL 65/35 Pozmix 10% Gel

2% Dixel Cement Blend and 130 sks 60/40 Pozmix 10% Gel 3% CC Lite Cement Blend

200# Hulls Allied Cement Co. B. and L. Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 PM Day: 2 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/200# Hulls in with 95 sks ATL Cement Blend to Anhydrite (1231) followed with 50 sks Lite Cement Blend to Max Psi 1000#. Close in Psi 1000#. Squeeze 8 5/8" annulus. Blew off head cement at surface. Plug complete.

A & M OIL, INC.
P.O. BOX 271
STOCKTON, KS 67669
CONTR CIRCLE M DRILLING

#2 CONN (A-4)

13-7-18W
NE NW NE

KCC

AUG 06 1998

CTY ROOKS
GEOL _____ FIELD RIFFE

+	+	+
+	+	+
+	+	+

ELV NA SPD 2/25/83 CARD ISSUED 2/16/84 IP P 15 BOPD & WTR
ARB OH - INTV NA

API 15-163-21,967

Tops _____ Depth/Datum _____
NO TOPS AVAILABLE
E RTD _____ 3500

E 8 5/8 " 250; PROD CSG NA
MICT - CO, (ARB OH), SWB DWN, GSO, POP, P 15 BOPD &
WTR, TIGHT HOLE - NO OTHER INFO TO BE RELEASED AT PRE-
SENT - WILL RELEASE INFO WHEN AVAILABLE - TEMP COMP -
2/16/84

NOTE: CORRECTION - ORIGINALLY FIRST REPORTED AS #3
CONN

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

FORM CP-2/3 LR
Rev. 01-84

8-5-98
RECEIVED
KANSAS CORP COM
1998 AUG -5 0 12:55
RECEIVED
KANSAS CORP COM
1998 AUG 12 0 12:18