

4-070083

1-14

API Number: 15-162-23,182 ¹⁶³ -20-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE NW NE /4 SEC. 13, 07 S, 18 W
4290 feet from S section line
1650 feet from E section line

Operator license# 31021
Operator: Castelli Exploration, Inc.
Address: 9500 Westgate Drive - #101
Oklahoma City, OK 73163

Lease: Westar Well # B-4
County: Rooks 110.60
Well total depth 3405 feet
Conductor Pipe: 13 3/8 inch @ 99'w/85 sxs.
Surface pipe 8 5/8 Inch @ 1337 feet
W/425 sxs.

ABAND. oil well , Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: Castelli Exploration, Inc. License# 31021

Address: 9500 Westgate Drive - #101 - Oklahoma City, OK 73163

Company to plug at: Hour: 12:00 P.M. Day: 14 Month: January Year: 1998

Plugging proposal received from: Tom Larson

Company: Castelli Exploration, Inc. Phone: -

Were: Dump 7 sxs sand with 5 sxs 60/40 pozmix - 10% gel on top. Shoot casing off and plug per KCC Rules and Regulations. 5 1/2" casing set at 3401' with 4' open hole.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 22 1998

1-22-98

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

CONSERVATION DIVISION
WICHITA, KS

Completed: Hour: 9:45 P.M., Day: 14, Month: January, Year: 1998

Actual plugging report: Dumped 7 sxs sand with 5 sxs cement on top. Shot casing off at 2091' - pulled to 1520'. Allied pumped 105 sxs 60/40 pozmix - 10% gel with 300# hulls. Pulled to 900' - pumped 40 sxs cement. Pulled to 400' cwc 95 sxs. Topped off with 5 sxs. Hole full.

Remarks: January 15, 1998 checked-fell back 60', called Tom Larson, filled with sand and cement cap.

Condition of casing(in hole): GOOD BAD _____
Bottom plug(in place): YES , CALC _____ , NO _____
Plugged through TUBING _____ , CASING .
Anhy.plug: YES NO _____
Dakota plug: YES , NO _____
Elevation: 1880 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 1-23-98
INV. NO. 49979

102