

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,200 ⁰⁰⁻⁰⁰

LEASE NAME State of Kansas

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section LI

330 Ft. from E Section LI

SEC. 24 TWP. 7 RGE. 18 XX or (W)

COUNTY Rooks

LEASE OPERATOR West - X, Inc.

ADDRESS 117 E. 13th, Hays, Kansas 67601

PHONE# (913) 625-3399 OPERATORS LICENSE NO. 3007

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed -

Plugging Commenced 9-29-92

Plugging Completed 11:45 AM

The plugging proposal was approved on 9-29-92 (date)
by Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation - Depth to Top 2705 Bottom 2709 T.D. 2709

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1185	0
				4 1/2	2705	2170
				13 3/8	60	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from - feet to - feet each
Bottom Plug: Sanded to 2650 & bailed 4 sx cement.

Top Plug: Shot casing at 2200 & pumped 100 sx cement (60/40 w/8%), Pulled 400 ft of casing & pumped 100 sx cement & 100 lbs Halls, pulled 400 ft casing & circulated 170 sx cement & 100 lbs Halls to surface. Pulled casing & pumped 30 sx cement w/800 lbs maximum & 600 lbs shut in.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: West - X, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke

(Employee of Operator West - X, Inc.)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fa statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres.

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 30 day of September, 1992



Anna K. Burke
Notary Public

My Commission Expires: 4-30-94

RECEIVED
STATE CORPORATION COMMISSION
102-92
OCT 2 1992

CIVIL DIVISION