

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19083-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 12-18S-11W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HERTACH Well #: 6
County: BARTON Total Vertical Depth: 3288 feet

Operator License No.: 31561
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM
Address: 410 B STREET PO BOX 531
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3285	0	UNKNOWN
SURF	8.625	274	0	UNKNOWN

80
\$106

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2005 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: C&K OIL COMPANY Phone: (620) 786-0644

Proposed Plugging Method: Ordered 450 sxs 60/40 poxmix -10% gel - 700# hulls.
Tubing and packer in the hole around 1900'.
Holes in casing. Milled out of casing at approximately 1800'.
Worked on well 12 days.
Emergency plug with rig over the hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2005 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

DS&W RIH with tubing to 1817'.
Allied rigged to tubing and pumped 300 sxs 60/40 pozmix with 500# hulls mixed in.
Pulled tubing to 1000' and pumped 50 sxs to circulate cement out of 5 1/2" casing.
Shut in 5 1/2" casing and pumped 45 sxs cement with 200# hulls mixed in to circulate cement out of 8 5/8" casing.
Slips had 400# P.I.P. No shut in pressure.
Casing standing full of cement.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #18455.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 11-9-05

INV. NO. 2006060925

RECEIVED

NOV 09 2005

KCC WICHITA

NOV 03 2005

INVOICE

KOCH OIL

#6

HERTACH

12-18-11W
NW NW SE

Contr. BIRMINGHAM-BARTLETT DR LG

BARTON

County

E 1786 RB

Comm.

Comp.

1-30-53

IP

3000 BOPD

DD

Tops	Depth	Datum
LANS	2995	-1209
ARB	3284	-1498
TD	3288	-1502

Casing

8" 274

5" 3285

DP, 800' FIH/1 HR;
SWB 15 BOPH
ACID 1000, SWB 20½
BOPH

ZINK POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS