

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21145-00-00
Spot: E2NW Sec/Twnshp/Rge: 36-9S-29W
1360 feet from N Section Line, 2070 feet from W Section Line
Lease Name: J F PRATT Well #: 1
County: SHERIDAN Total Vertical Depth: 4250 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: RR 2, BOX 14
WAKEENEY, KS 67672

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 8.625 | 265 | | |

#138¹³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/04/2005 4:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix- 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 11/04/2005 4:45 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

1st. Plug at 2450' w/25 sxs.
2nd. Plug at 1580' w/100 sxs.
3rd. Plug at 315' w/ 40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce Basye
(TECHNICIAN)

1000
INVOICED

RECEIVED

DATE 11-9-05

NOV 09 2005

INV. NO. 2006060728

KCC WICHITA

NOV 07 2005