

4-060343

9-29

*11 R*

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23,200-00-00

SE SE SE /4 SEC. 24, 07 S, 18 W  
330 feet from S section line  
330 feet from E section line

Operator license# 3007

Lease State of Kansas well # 1

Operator: West X, Inc.

County Rooks

Address: P.O. Box 126  
Hays, Kansas 67601

Well total depth 2709 feet *88.04*  
Conductor Pipe: 13 3/8 inch @ 60 feet  
Surface pipe 8 5/8 Inch @ 1185 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Great Bend Casing Pullers License# 4635

Address: Box 768 - Great Bend, Kansas 67530

Company to plug at: Hour: 8:30A.M. Day: 29 Month: September Year: 92

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers Phone: 316-793-9711

Were: Order 400 sxs. 60/40 posmix - 8% gel. and hulls.  
Plug through casing.  
Plug back to 2650' with sand and spot 4 sxs. cement with bailer.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:45A.M., Day: 29, Month: September, Year: 92

Actual plugging report: 13 3/8" at 60'. 8 5/8" at 1185'. 4 1/2" to 2700'. Sanded back to 2650' and spotted 4 sxs. cement with dump bailer. Shot one time and recovered 2217' casing. At 2217' mix and pump 100 sxs. cement. Pull 400' of casing and pump 100 sxs. cement. Pull 400' casing and circulate cement to surface with 170 sxs. cement. Pulled casing and tied onto surface pipe. Pumped 30 sxs. cement. Max. pressure 800#. S.I.P. 600#.

Remarks: Allied Cementing

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO    

Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO    

Plugged through TUBING    , CASING X. Elevation: 1750 GL

I did not observe the plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 8 1992  
10-8-92  
CONSERVATION DIVISION  
Wichita, Kansas  
*E.A.S.*

DATE 10-30-92

(agent)

INV. NO. 36515