

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22741-00-00
Spot: SWSESW Sec/Twnshp/Rge: 3-9S-19W
330 feet from S Section Line, 1650 feet from W Section Line
Lease Name: ROSTOCIL A Well #: 7
County: ROOKS Total Vertical Depth: 3445 feet

Operator License No.: 5552

Op Name: GORE OIL COMPANY

Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	2.875	3375	0	
PROD	5.5	3442	0	135 SX CMT
SURF	8.625	767	0	300 SX CMT

96
\$ 111

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/02/2005 4:00 PM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: LENNY DINKEL

Company: GORE OIL COMPANY

Phone: (316) 263-3535

Proposed Plugging Method: Ordered 200 sxs Swift Multi-Density Cement and 500# hulls.
Squeeze jobs: 1990 - 963'-1916' w/480 sxs; 1991-1134'-1318' w/100 sxs; 1992 - 1239' - 1333' w/30 sxs.
2 7/8" tubing cemented in at 3375' w/225 sxs SMD - 40 sxs to pit.
Developed new leaks 1106' - 1905' - pump in at 2.5 bpm at 400#.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/02/2005 5:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Tied onto tubing and pumped 25 sxs Swift Multi-Density neat, followed with 55 sxs SMD with 450# hulls.
Max. P.S.I. 500#. S.I.P. 250#.
Hooked up to backside and pumped 25 sxs SMD.
Max. P.S.I. 500#. S.I.P. 400#.

RECEIVED
NOV 14 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED


DATE 11-14-05
NO. 2006060734

NOV 07 2005

~~CONFIDENTIAL~~
~~CONFIDENTIAL~~
INDEXED

SOHIO PETROLEUM COMPANY
 50 PENN PLACE, #1100 #7 'A' ROSTOCIL 3-9-19W
 OKLAHOMA CITY, OK 73118 SW SE SW
 CONTR ALLEN DRILLING CTY ROCKS
 GEOL STEVE BRACHMAN FIELD BARRY

ELV 2029 KB SPD 9/8/85 ^{CARD} ISSUED 10/31/85 IP P 57 B0 & 29 BWPD
 2014 GL DRLG COMP 9/24/85 ARB OH 3442-3445



LOG	Tops Depth/Datum	API 15-163-22,741
ANH	1432+ 597	8 5/8 " 767 / 300SX, 5 1/2 " 3442 / 135SX NO CORES OR DSTS MICT - CO. (ARB OH), SWB DWN, NAT, T&R, POP, P 57 B0 & 29 BWPB, 10/9/85
B/ANH	1471+ 558	
TOP LM	2946- 917	
HEEB SH	3150-1121	
TOR LM	3172-1143	
LANS	3191-1162	
BKC	3416-1387	
ARB	3441-1412	
RTD	3445-1416	

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS