

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21161-00-00⁰¹
Spot: SENENW Sec/Twnshp/Rge: 18-9S-23W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ALBERTSON Well #: 4
County: GRAHAM Total Vertical Depth: 3950 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3948	0	150 SX CMT
SURF	8.625	203	0	165 SX CMT

38
#128

Well Type: EOR UIC Docket No: E23923.3 Date/Time to Plug: 06/30/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 13 sxs gel.
DV at 2030' with 475 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2005 10:30 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

4 1/2" production casing set at 3948' w/150 sxs cement.
8 5/8" surface casing set at 203' w/165 sxs cement.
Rigged up cementers and squeezed 25 sxs cement with 200# hulls,
followed with 13 sxs gel and 125 sxs cement with 200# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
8 5/8" - pressured up 500#. No cement pumped.

Perfs:

Top	Bot	Thru	Comments
3870	3876		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

INVOICED

RECEIVED

DATE 9-21-05

SEP 20 2005

INV. NO 2006060460

KCC WICHITA

SEP 14 2005

JOHN O FARMER INC. 18-9-23W
 BOX 352 #4 ALBERTSON SE NE NW
 RUSSELL, KS 67665

CONTR JOHN O FARMER CTY GRAHAM

GEOL FIELD ERNST NW

E 2370 KB CM 9/13/80 CARD 12/11/80 IP P 20 BOPD, NW
 ISSUED LANS 3870-76

API 15-065-21,161

LOG	TOPS	DEPTH	DATUM
ANH	2038	+ 332	
HEEB	3675	-1305	
TOR	3700	-1330	
LANS	3717	-1347	
B LANS	3948	-1578	
LTD	3950	-1580	

8 5/8" 203/165sx; 4 1/2" 3948/150sx

DST (1) 3855-75/30-60-90-90, 120' GAS
 75' HOCM, SIP 305-283#, FP 43-43#
 DST (2) 3874-3920/30-30-30, 181' VSO
 STAINED M, SIP 954-694#, FP 43-53/
 55-54#

MICT - CO, PF 3870-76, AC 2000, SWB
 LD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

63210VW!

1111 1111

1111 1111