

To: **6 040995**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-25
API NUMBER 15-163-22508-00-00
SE NE NE, SEC. 24, T 7 S, R 18 W/Ex

4290 feet from (S) section line
330 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # NA 101

Lease Name Marshall Well # 1 J - 6

Operator: KCC Fee Fund

County Rooks

Name & Address Baker Oil Operations

Well Total Depth 3272 feet

Jay Baker

Conductor Pipe: Size 13 3/8 feet 94' cwc

Codell, Kansas

Surface Casing: Size 8 5/8 feet 1222' cwc

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Ks.

Company to plug at: Hour: AM Day: 25 Month: Oct Year: 19 88

Plugging proposal received from

(company name) (phone)

were: 5 1/2" casing set at 3270' w/NA sks. Top perf at N.A. Ordered 300 sks 65/35 Poz
10% Gel w/2% Dicol.

RECEIVED
STATE CORPORATION COMMISSION
12-29-88
DEC 29 1988

Plugging Proposal Received by Dennis L. Hamel
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 25 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 195 sks cement plus 4 sks Hulls mixed in
cement. Max 1500#. S.I. 500# psi. Pumped in 8 5/8" casing - 20 sks at 4 sks per bbl.
followed w/60 sks at 2.5 sks per bbl followed w/25 sks at 5 sks per bbl.

Max psi 1000#. Shut in 600#: Returned Oct. 26, 1988. Checked cement in 5 1/2" casing and
surface pipe, o.K.: Casing cut off and location leveled. Job completed.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis Hamel