

4-041777

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

7-16

API Number: 15-163-22,212

00-00

NW NE NE /4 SEC. 24, 07 S, 18 W  
270 feet from N section line  
903 feet from E section line

Operator license# 5506

Lease: MWM (Cos I-5) Well # 1-5

Operator: Woolsey Petroleum Corpation

County: Rooks 106173

Address: 107 North Market - #600  
Wichita, Kansas 67202

Well total depth 3284 feet  
Conductor Pipe: 13 3/8 inch @ 90 feet  
Surface pipe 8 5/8 Inch @ 1222 feet  
w/425 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 16 Month: July Year 1996

Plugging proposal received from: Carl W. Durr

Company: Woolsey Petroleum Corporation Phone: 316-886-5606

Were: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
5 1/2" set at 3282' w/150 sxs.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:00P.M., Day: 16, Month: July, Year: 1996

Actual plugging report: Checked surface casing annulus for cement fillup. Pumped down 5 1/2" casing - pumped 25 sxs 60/40 pozmix - 10% gel - 300# hulls. Followed up with 250 sxs 60/40 pozmix - 10% gel plus 200# hulls. Max. P.S.I. 600#. S.I.P. 500#.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 22 1996

Remarks: Allied Cementing.

Condition of casing (in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug (in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE JUL 25 1996

INV. NO. 46106

7-16 SEP 27 1996