

To: 6 030963
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 5900
Operator: Lawbanco Drilling Company
Name & Address Box 289
Natoma, Kansas 67651

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 2 Month: October Year: 19 87

Plugging proposal received from Mike Kelso

(company name) Kelso Casing (phone) _____

were: 8 5/8" set at 1231' w/425 sks. 5 1/2" set at 3306' w/150 sks. Perfs - Order
90 sks ATL 65/35 Pozmix 10% Gel 2% Dical Cement Blend and 130 sks. 60/40 Pozmix 10% Gel
3% Cal Cl Lite Cement Blend 200# Hulls. Allied Cement Co. B and L Water Trucks.

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 2 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/200# Hulls in with 90 sks ATL Cement Blend
to anhydrite (1231') followed with 50 sks Lite Cement Blend to Max PSI 1000# Close in PSI
1000#. Squeeze 8 5/8" annulus w-80 sks Lite Cement Blend to Max PSI 1000# Close in PSI
1000# Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1987
10-23-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 10-26-87
INV. NO. 1860365

10-2-87
API NUMBER 15- 163-22,148 -00-00
NE NE NE, SEC. 24, T 7 S, R 18 W/E
330 2310 feet from N section line
330 feet from E section line
Lease Name MWN Well # I-6
County Rooks 107.51
Well Total Depth 3308 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1231

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow