

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21,970 -00-00R

NW-1/4-SE, Sec. 24, T 7 S, R 18(W)E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5562

Lease Name Cooperation Inc Well # 1

Operator:  
Name & Address Liberty Enterprises Inc.  
Plainville, Kansas  
67663

County Rooks

Well Total Depth 3350 feet 108.88

Conductor Pipe: Size 13 3/8 feet 81 w/90.24

Surface Casing: Size 8 1/2 feet 1204 w/75.24 comm

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A 350.24 60/40 pgs

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing & Allied Emty License Number \_\_\_\_\_

Address Chase & Russell, Kansas

Company to plug at: Hour: 11:45 AM Day: 31 Month: 5 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 5 1/2" set @ 3350' w/175 sx P.B. @ 3200'

Top Perf 3062' P. Bottom w/5 sx emt - sand to 3000' -

+5 sx emt, Recovered approximately 2100' of 5 1/2" cas.

Ordered 190 sx 1 1/2 poz, 8% gel, 3% cc; 20 sx gel; 4 sx hulls

& W. plug

Signed Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 AM Day: 31 Month: 5 Year: 1984

ACTUAL PLUGGING REPORT

Rmpd in 8 1/2" S.P. -> 4sx hulls -> 8sx gel -> 40 sx emt (P.S.I to

1000#) rmpd additional 20 sx emt (trike down) -> 12 gel ->

R. Plug -> rmpd add 100 sx emt -> P.S.I to 1300#

shut down. Shut-in @ 1300# P.S.I.

May - 1500# P.S.I

Remarks: \_\_\_\_\_

6-4-84  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 04 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE 6-5-84

INV. NO. 1913