

4-041744

12-27

API Number: 15-163-21,606 - 00-00

Tó: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW SW SE /4 SEC. 24, 07 S, 18 W
330 feet from S section line
2310 feet from E section line

Operator license# 5635

Lease: Folsom-Richardson Well # 1

Operator: The Gene Brown Company

County: Rooks

Address: P.O. Drawer 220
Plainville, Kansas 67663

Well total depth 3314 107.71 feet
Conductor Pipe: 13 7/8 inch @ 89w/210sx feet
Surface pipe 8 5/8 Inch @ 1207 feet
w/425 sxs

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 27 Month: December Year 1995

Plugging proposal received from: Tom Brown

Company: The Gene Brown Company Phone:

Were: 5 1/2" casing set at 3314' w/150 sxs cement. Perfs at 2706' - 3128'.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls - plus 12 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:00 A.M., Day: 27, Month: December, Year: 1995

Actual plugging report: Pulled rods and tubing. R.U. Cementers to squeeze 5 1/2" casing with 35 sxs cement with 200# hulls, followed with 12 sxs gel, followed with 125 sxs cement. Max. P.S.I. 1000#. S.I.P. 500#. Pumped down 8 5/8" S.P. with 75 sxs cement with 100# hulls. Max. P.S.I. 700#. S.I.P. 300#.

Remarks:

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

INVOICED

DATE JAN 12 1996

INV. NO. 44548

RECEIVED STATE CORPORATION COMMISSION (agent) Dennis L. Hamel
FORM CP-1296 1-8-96
CONSERVATION DIVISION WICHITA, KANSAS