

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01745-00-00
Spot: SWNWE Sec/Twnshp/Rge: 27-21S-13W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: R C GATES Well #: 13
County: STAFFORD Total Vertical Depth: 3681 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3671	0	WITH 250 SX CMT
SURF	8.625	269		WITH 250 SX CMT

#11963

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2005 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: RALPH STALCUP Company: GLOBE OPERATING Phone: (620) 792-7607

Proposed Plugging Method: SET CIBP & 2 SX CMT @ 3420' OR RUN TUBING TO 3420' & SPOT 10 SX GEL - 50 SX CMT. PERFORATE @ 800'. RUN TUBING. CIRCULATE CMT TO SURFACE UP 5 1/2" & 5 1/2" X 8 5/8".

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2005 9:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE 750'. SFL 60'. WORKED TUBING THROUGH PARTED CASING @ 320' & 680'. GOT TUBING TO 730' & COULD NOT GET ANY FARTHER. RAN TUBING TO 720' & PUMPED 415 SX CMT. GOOD CIRCULATION UP 5 1/2" & 5 1/2" X 8 5/8" ANNULUS. NO CMT. SDON. 11/3/05: TAGGED CMT WITH TUBING @ 420'. PUMPED 200 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. PULLED TUBING. TOPPED OFF 5 1/2" WITH 4 SX CMT 8 5/8" X 5 1/2" STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
3473	3480		


INVOICED

DATE 11-15-05
INV NO 2006060736

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
NOV 15 2005
KCC WICHITA

Form CP-2/3