

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-19019-00-03  
Spot: SENENW Sec/Twnshp/Rge: 13-25S-13W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SOUTH LEESBURG UNIT Well #: 102  
County: STAFFORD Total Vertical Depth: 4124 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: PO BOX 729 - 102 S. RIVER ROAD  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3493		
PROD	7	4114	0	WITH 475 SX CMT
SURF	10.75	278		WITH 225 SX CMT

# 134<sup>03</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2005 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 2900' & 7 SX CMT. PERFORATE AT 730'. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2005 3:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE 710-745'. SANDED TO 2900' & 7 SX CMT WITH BAILER. PERFORATED 7" @ 730'. PUMPED 450 SX CMT DOWN 7". GOOD CIRCULATION THROUGHOUT JOB BUT NO CMT TO SURFACE UP 7" X 10 3/4" ANNULUS. 11/01/05: PUMPED 100 SX CMT DOWN 10 3/4" X 7" ANNULUS. PRESSURED TO 500 PSIG. TOPPED OFF 7" WITH 50 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3072	3078		

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

**INVOICED**  
DATE 11-15-05  
INV. NO. 2006060738

District: 01



Signed

Richard W. Lacy

(TECHNICIAN)

RECEIVED  
NOV 15 2005  
KCC WICHITA

Form CP-2/3