

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21275-00-00
Spot: NWSE Sec/Twnshp/Rge: 4-29S-12W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: NEEL Well #: 2
County: PRATT Total Vertical Depth: 4565 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4564	2650	WITH 225 SX CMT
SURF	8.625	380		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2005 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3941' & 5 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 410' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2005 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3941' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 700' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 410' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4259	4261		
4220	4222		
4205	4208		
4170	4174		
4007	4010		


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

DATE 11-15-05
INV. NO. 2006060740

Plugged through: CSG

District: 01



Signed

Steve Pfeifer
(TECHNICIAN)

RECEIVED
NOV 15 2005
KCC WICHITA