

6040194

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,472 R-00-00
C SW $\frac{1}{4}$, SEC. 18, T 7 S, R 18 W/E
1445 feet ^N from SE section line
4310 feet ^E from SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6867

Lease Name LaBarge Well # 1

Operator: Steinle Oil Operations

County Rooks

Name & Address 624 E. 3rd Street

Well Total Depth 3400 110.50 feet

Russell, Ks.

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 $\frac{5}{8}$ feet 251' w/160

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Drilling License Number 8241

Address _____

Company to plug at: Hour: 6:15 AM Day: 28 Month: September Year: 19 84

Plugging proposal received from Nick Kreutzer

(company name) Emphasis Drilling (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls and 8 $\frac{5}{8}$ " plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 6:15 AM Day: 28 Month: September Year: 19 84

ACTUAL PLUGGING REPORT

- 1st plug @ 1875 w/40 sks
- 2nd plug @ 350 w/100 sks & 1 sk hulls
- 3rd plug @ 260' w/40 sks
- 4th plug @ 40 w/10 sks (solid bridge)
- 10 sks in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION
10-9-84
OCT 09 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

(If not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN) 10-5-84

INVOICED
DATE 10-11-84
INV. NO. 4949