

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED

MAR 11 2003

KCC WICHITA

3-11-2003

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-163-23,005-00-02
LEASE NAME KU Endowment
WELL NUMBER 3
2310 ft. from ^N Section Line
1650 ft. from E Section Line
SEC. 25 TWP. 7 RGE. 18 or (W)
COUNTY Rooks

LEASE OPERATOR Black Diamond Oil, Inc.
ADDEESS PO Box 641, Hays, KS 67601
PHONE # (785) 625-5891 OPERATORS LICENSE NO. 7076
Character of well oil

Date Well Completed
Plugging Commenced 12/4/02
Plugging Completed 12/6/02

(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 12/4/02 (date)
by Herb Deines (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? Sent with well plugging application

Producing Formation Arbuckle Depth to Top 3221 Bottom 3480 T.D. 3480

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Water/Oil	3250	3274	8 5/8	1142	none
				5 1/2	3460	1518

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set

Sand bottom, bail 5 sks cem. Shot pipe at 2400, 2221, 2031, 1518, came free. Pull to 1400, pump 100 sks cem, 3 sks hulls. Pull to 1150, pump 40 sks cem and 1 sk hulls. Pull to 650, pump 30 sks cem. Pull to 200, pump 50 sks cem. Circulate to surface

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.


(Signature) *Kenneth Vehige*

(Address) P.O. Box 641

SUBSCRIBED AND SWORN TO before me 28th day of February, 2003

Verda M. Brin
Notary Public Verda M. Brin

My commission Expires: 7-18-2003



ALLIED CEMENTING CO., INC. 11530

Federal Tax I.D.# XXXXXXXXXX

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

15-163-23005-00-00

DATE <u>12-4-02</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
<u>KV.</u>					<u>4:30 PM</u>	<u>5:00 PM</u>	<u>7:00 PM</u>
LEASE # <u>END</u>	WELL # <u>3</u>	LOCATION <u>STOCKTON S.S.</u>			COUNTY <u>ROOKS</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR QUALITY

TYPE OF JOB PTA

HOLE SIZE 7 7/8 T.D.

CASING SIZE 5/2 DEPTH

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT

OWNER

CEMENT

AMOUNT ORDERED 225 60/40 10% GEL

400# HULLS

USED 220 SKS

COMMON	<u>132</u>	@	<u>665</u>	<u>877.80</u>
POZMIX	<u>88</u>	@	<u>355</u>	<u>312.40</u>
GEL	<u>16</u>	@	<u>10.00</u>	<u>160.00</u>
CHLORIDE		@		
<u>Hulls</u>	<u>4</u>	@	<u>18.00</u>	<u>72.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>225</u>	@	<u>1.10</u>	<u>247.50</u>
MILEAGE	<u>44 1/2</u>	@	<u>8.00</u>	<u>360.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER MARK

346 HELPER BILL

BULK TRUCK

362 DRIVER SHANE

BULK TRUCK

DRIVER

TOTAL 2029.70

REMARKS:

SERVICE

100 SKS @ 1400 W/300# HULLS

40 SKS @ 1100 W/100# HULLS

30 SKS @ 600

50 SKS @ 200 CIRC CEMENT

DEPTH OF JOB

PUMP TRUCK CHARGE 475.00

EXTRA FOOTAGE @

MILEAGE 40 @ 3.00 120.00

PLUG @

TOTAL 595.00

CHARGE TO: BLACK DIAMONDS

STREET

CITY STATE ZIP

FLOAT EQUIPMENT

@

@

@

@

@

RECEIVED

MAR 11 2003

KCC WICHITA

To Allied Cementing Co., Inc.