

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Falcon Exploration, Inc.
Address: 155 N. Market, Suite 1020; Wichita, KS 67202
Phone: (316) 262-1378 Operator License #: 5316
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 09/11/05 (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
WILL BE MAILED WITH ACO-1.
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-025-21298-00-00
Lease Name: Decker
Well Number: #2
Spot Location (QQQQ): NE - NE - NW -
550 Feet from North / South Section Line
2440 Feet from East / West Section Line
Sec. 12 Twp. 31 S. R. 22 East West
County: Clark
Date Well Completed: 09/11/05
Plugging Commenced: 09/11/05
Plugging Completed: 09/12/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	80'	20"	82'	0
		0	835'	8 5/8"	830'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

pump 40 sx 60:40:6 at 6475'; Disp. with 3 bbls fresh H2O and 83 bbls mud; pump 80 sx 60:40:6 at 1020'; Disp. with 3 bbls fresh H2O and 4 bbls mud; pump 40 sx 60:40:6 at 300'; Disp. with 1 bbl fresh H2O; pump 20 sx 60:40:6 at 60', Plug ratihole with 15 sx and mouse hole with 10 sx 60:40:6.

RECEIVED

NOV 14 2005

KCC WICHITA

Name of Plugging Contractor: Val Energy, Inc. License #: 5822

Address: 200 W. Douglas, Ste. 520; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Falcon Exploration, Inc.


State of Kansas County, Sedgwick, ss.

Ron Schraeder

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Ronald P Schraeder

(Address) Falcon Exploration, Inc.; 155 N. Market, Ste. 1020; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 2nd day of November, 2005

Rosann M Schippers My Commission Expires: 9/28/07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Ben

ALLIED CEMENTING CO., INC.

16381

Federal Tax I.D.# ~~45-0711000~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Med Lodge KS

DATE <u>09-11-05</u>	SEC. <u>12</u>	TWP. <u>31s</u>	RANGE <u>22w</u>	CALLED OUT <u>09:30 Am</u>	ON LOCATION <u>1:00pm</u>	JOB START <u>2:30pm</u>	JOB FINISH <u>12:15 Am</u>
LEASE <u>Decker</u>	WELL # <u>2</u>	LOCATION <u>183 & 345th, 1 1/2 W, 2 W/1m</u>			COUNTY <u>Clark</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)							

CONTRACTOR Val #2
 TYPE OF JOB Rotary Plug
 HOLE SIZE 7 7/8 T.D. 6475'
 CASING SIZE _____ DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2 DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 500 MINIMUM 100
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT Mud & Fresh H₂O

OWNER Falcon Exploration
 CEMENT
 AMOUNT ORDERED 205 of 60:40:6

COMMON	<u>123</u>	<u>A</u>	@	<u>8.70</u>	<u>1070.10</u>
POZMIX	<u>82</u>		@	<u>4.70</u>	<u>385.40</u>
GEL	<u>11</u>		@	<u>14.00</u>	<u>154.00</u>
CHLORIDE			@		
ASC			@		
			@		
			@		
			@		
			@		
			@		
			@		
			@		
			@		
			@		
			@		
HANDLING	<u>216</u>		@	<u>1.60</u>	<u>345.60</u>
MILEAGE	<u>55 x 216 x .06</u>				<u>712.80</u>
					TOTAL <u>2667.90</u>

EQUIPMENT

PUMP TRUCK CEMENTER P. Falio
 # 397 HELPER C. Reed
 BULK TRUCK
 # 363 DRIVER T. Damico
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

Pump 40 sk 60:40:6 at 6475' Disp with 3 Bbls Fresh H₂O & 83 Bbls mud, Pump 80 sk 60:40:6 at 1020' Disp with 3 Bbls Fresh H₂O & 4 Bbls mud, Pump 40 sk 60:40:6 at 300' Disp with 1 Bbls Fresh H₂O, Pump 20 sk 60:40:6 at 60', Plug out hole with 15 sk and move hole with 10 sk 60:40:6

SERVICE

DEPTH OF JOB 6475'
 PUMP TRUCK CHARGE _____ 1800.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 55 @ 5.00 275.00
 _____ @ _____
 _____ @ _____
 _____ @ _____

CHARGE TO: Falcon Exploration
 STREET _____
 CITY _____ STATE _____ ZIP _____

RECEIVED
 NOV 14 2005
 KCC WICHITA

TOTAL 2075.00

PLUG & FLOAT EQUIPMENT

MANIFOLD _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE ~~_____~~
 DISCOUNT ~~_____~~ IF PAID IN 30 DAYS

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SIGNATURE Leo Roberts

Leo Roberts
 PRINTED NAME