

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

#4 ✓ 15-163-20055-00-00  
 API NUMBER 9-19-67

RECEIVED  
 STATE CORPORATION COMMISSION  
 9-12-88  
 SEP 12 1988

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
office within 30 days.

LEASE NAME BRAY

WELL NUMBER #1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 35 TWP. 7 RGE. 18 (E) or (W)

COUNTY ROOKS

Date Well Completed 1/13/70

Plugging Commenced 9/1/88

Plugging Completed 9/1/88

LEASE OPERATOR J. MARK RICHARDSON  
 ADDRESS 640 CENTURY PLAZA 111 W. DOUGLAS WICHITA, KS. 67202

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS, KS.

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation LANSING Depth to Top 3166 Bottom 3168 T.D. 3392

Snow depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
ARBUCKLE	OIL	0	3392	4 1/2	3392	NONE
		0	200	85/8	200	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

perf 4 1/2 cs. @ 1350' 4 holes and perf @700' 3 holes. Cement with 250 sks 8%gd 60/40 poy, 1/4# flow seal and 5 sk hull 550# max press ISIP 300#, perf. @50' cement with 100 sks 60/40 poy 8%gel 3 sk hull @ 300# ISIP 175#

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON SERVICES License No. \_\_\_\_\_

Address HAYS,

STATE OF KANSAS COUNTY OF ELLIS, ss.

J. MARK RICHARDSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 640 CENTURY PLAZA, WICHITA, KS.

SUBSCRIBED AND SWORN TO before me this 9TH day of SEPTEMBER, 19 88

[Signature]  
 KIM SANTELLAN  
 Notary Public

My Commission Expires: 2/22/92

