

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-163-21818-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Rooks SEC. 29 TWP. 7S RGE. 18 (E/W)
 Location as in quarters or footage from lines:
660' FSL 660' FEL

Lease Owner Eagle Explorations, Inc.
 Lease Name Eisenhauer Well No. #1
 Office Address Suite 300, 107 N. Market Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 10-16-82
 Application for plugging filed 10-19-82
 Plugging commenced 10-16-82 5:00 P.M.
 Plugging completed 10-16-82 11:15 P.M.
 Reason for abandonment of well or producing formation Dry Hole

Locate Well correctly on above Section Platt.

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Butcher

Producing formation None Depth to top _____ bottom _____ T.D. 3445'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				13 3/8"	226'	None
Dakota	Water	600'	1237'	8 5/8"	1257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 4" Drill pipe to 3445', Pumped 15 Saxes Cement, Plug #1 from 3445' to 3374'
Pumped 15 Saxes Cement, Plug #2 from 1244' to 1177'
70 Saxes Cement, Plug #3 from 720' to 405'
10 Saxes Cement & Wood, Plug from 40' to surface
10 Saxes Cement in rat hole
10 Saxes Cement in mouse hole
Cement used: 130 Saxes 50:50 Pozmix 4% Gel.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 22 1982

CONSERVATION DIVISION
 Wichita, Kansas


10-22-82

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor _____

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
CARL DURR (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Durr
107 N MARKET WICHITA KS.
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 82



Sharon I. Clark
 Sharon I. Clark Notary Public.

My Commission expires: _____