

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR C. C. & S. Oil Operations, Inc.

API NO. 15-163-21,630 - 00-00

ADDRESS 12 Northridge Plaza

COUNTY Rooks

Hays, Ks. 67601

FIELD Riffe

**CONTACT PERSON Daniel Schippers

PROD. FORMATION Arbuckle

PHONE (913) 628-3284

LEASE E. Smith

PURCHASER CRA, Inc.

WELL NO. 1

ADDRESS P. O. Box

WELL LOCATION NW SW NW

Kansas City, Mo. 64116

DRILLING Contractor Lawbanco Drilling Co.

Ft. from Line and

CONTRACTOR ADDRESS P. O. Box 289


Ft. from Line of

Natoma, Ks. 67651

the NW/4 SEC. 36 TWP. 7 RGE. 18W

PLUGGING CONTRACTOR ADDRESS

WELL PLAT



KCC KGS (Office Use)

TOTAL DEPTH 3380 PBT

SPUD DATE 4/12/82 DATE COMPLETED 4/20/82

ELEV: GR 1827' DF 1829' KB 1832'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 1234' DV Tool Used? NO

AFFIDAVIT

STATE OF Kansas, COUNTY OF Ellis, ss, I,

Daniel F. Schippers OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES THAT HE IS Controller (FOR)(OF) C. C. & S. Oil Operations, Inc.


OPERATOR OF THE E. Smith LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 22nd DAY OF May, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.



SUBSCRIBED AND SWORN BEFORE ME THIS 1st DAY OF June, 19 82

(S) Daniel F. Schippers Daniel F. Schippers

MY COMMISSION EXPIRES: 8-11-85

Robin K. McDowell NOTARY PUBLIC Robin K. McDowell

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Production Area.

62-82 RECEIVED CORPORATION COMMISSION COMMUNICATION DIVISION - 2 1982

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1224'			
Base Anhydrite	1263'			
Topeka	2757'	2758'		
Heebner	2971	2970'		
Toronto	2995	2992'		
Lansing-K.C.	3013	3012		
Base-K.C.	3234	3233		
Marmaton	3264	3266		
Arbuckle	3290	3290		
T.D.	3380	3380		

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24	1234'	Common	325	2% gel 3% cc
Production	7 7/8"	5 1/2"	14	3380'	ASC	125	ASC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	JET	3314-3322

TUBING RECORD		
Size	Setting depth	Packer set at
2 7/8"	3265.55	-----

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
NONE	

Date of first production May 22, 1982	Producing method (flowing, pumping, gas lift, etc.) pumping	Gravity 28.5
RATE OF PRODUCTION PER 24 HOURS	Oil 10 bbls.	Gas 30 bbls.
Disposition of gas (vented, used on lease or sold)	Water 75 %	Gas-oil ratio 30 CFPB
	Perforations	