

RECEIVED
OCT 17 2005
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 093-20304 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date spud 6/14/76

Well Operator: XTO Energy, Inc. KCC License #: 32864
Address: 210 Park Ave., Suite 2350 (Owner / Company Name) City: Oklahoma City (Operator's)

State: Oklahoma Zip Code: 73102 Contact Phone: (405) 319 - 3212

Lease: Masonic Home Well #: 4-2 Sec. 35 Twp. 25 S. R. 36 East West

SW - SW - NE Spot Location / QQQQ County: Keamy

2590' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2490' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 575' Cemented with: 300 Sacks

Production Casing Size: 4 1/2" Set at: 3017' Cemented with: 700 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2706' - 16', 2722' - 28', 2740' - 46', 2752' - 56', 2762' - 66', 2770' - 74', 2792' - 96'

Elevation: 3036' (G.L. / K.B.) T.D.: 3021' PBTD: 3017' Anhydrite Depth: 1233'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill hole w/ 9# mud, set BP +/- 50' of perms (2656') w/ 100' cmt on top, surface csg 200' cement plug from 475' - 675', surface plug from 34' to 4'.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No
If not explain why? Unknown

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Littell or Mark Gosch
Phone: (620) 355 - 7838

Address: 805 S. Hwy 25 City / State: Lakin, KS 67860

Plugging Contractor: Sargent & Horton KCC License #: 31151
(Company Name) (Contractor's)

Address: RT 1, BOX 49 BA, TYRONNE, OK 73951-9731 Phone: (580) 854-6515

Proposed Date and Hour of Plugging (if known?): Unknown at present

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 10/13/05 Authorized Operator / Agent: Karen Byers
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

6/06

1/06

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

XTO Energy Inc.
210 Park Avenue - Suite 2350
Oklahoma City, OK 73102

November 15, 2005

Re: MASONIC HOME #4-2
API 15-093-20304-00-00
SWSWSWNE 35-25S-36W, 2590 FNL 2490 FEL
KEARNY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888