

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22536-00-01
Spot: SENWNW Sec/Twnshp/Rge: 10-7S-20W
4920 feet from S Section Line, 4920 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 7-6
County: ROOKS Total Vertical Depth: 3700 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 218 160 sx cmt 8/20.25
Production: Size 4.5 feet: 3643 275 DV @1692 550 SX
Liner: Size feet:

Well Type: EOR UIC Docket No: E25885.4 Date/Time to Plug: 10/04/2001 10:30 AM
Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC
Proposal Rcvd. from: JAMES B. DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 10% gel - 400# hulls - 8 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/04/2001 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

4 1/2" casing - squeezed down 25 sxs 60/40 pozmix - 10% gel with 300# hulls,
followed with 8 sxs gel, followed with 125 sxs cement with 100# hulls.
8 5/8" S.P. Pressured up to 500#.

Remarks: LEASE ALSO KNOWN AS PROBASCO #A-6. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

RECEIVED

OCT 16 2001

KCC WICHITA

INVOICED

DATE 10-16-01

INV. NO. 2002060810

Form CP-2/3


OCT 15 2001

REPLACEMENT CARD

FRONTIER OIL COMPANY
 1720 KSB&T BLDG. WICHITA, KS. 67202
 #6 'A' PROBASCO
 10-7-20W
 SE NW NW

CONTR RED TIGER DRILLING CTY ROOKS
 GEOL RICHARD D. PARKER FIELD PROBASCO

ELV 2090 KB SPD 10/26/84 CARD ISSUED 3/28/85 IP P 34 BOPD, NW
2085 GL DRLG COMP 11/1/84 LKC 3467-3484 OA
 API 15-163-22,536



SMP	Tops	Depth/Datum
ANH	1650+ 440
TOP	3075- 985
HEEB	3282-1192
TOR	3304-1214
LANS	3318-1228
BKC	3520-1430
ARB	3560-1470
REAG	3680-1590
GRAN WSH	3685-1595
GRAN	3695-1605
RTD	3700-1610

8 5/8 5" 218 / 160SX, 4 1/2 " 3643 / 275SX, DV TOOL AT 1692 / 550SX
 NO CORES OR DSTS
 MICT - CO, PF (LKC) 1 / 3467 & 1 / 3484, AC 1000 GAL (15%
 DEMUL), SWB LD, SO, RE-AC 4000 GAL (7.5% MCA), SO, SET
 2 3/8 " TBG AT 3450, POP, P 34 BOPD, NW, 12/8/84

INFO RELEASED: 7/3/86 - WAS OIL WELL - TIGHT HOLE