

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22526-00-01 *103 KCC OP*
Spot: NENWNE Sec/Twnshp/Rge: 10-7S-20W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 8-2
County: ROOKS Total Vertical Depth: 3678 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 333 210 SX CMT
Production: Size 5.5 feet: 1537 350 SX CMT
Liner: Size feet:
8/119.54

Well Type: WSW UIC Docket No: Date/Time to Plug: 10/04/2001 7:30 AM
Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed Plugging Method: According to KCC Rules and Regulations.
Ordered 150 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/04/2001 9:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 333' w/210 sxs cement.
5 1/2" casing at 1537' w/350 sxs cement.
Tied to 5 1/2" casing - pumped 150 sxs cement with 400# hulls to Max. P.S.I. 700#. S.I.P. 700#.
Tied to 8 5/8" annulus - took no cement - locked immediately.
Total of 150 sxs 60/40 pozmix - 10% gel and 400# hulls.

Remarks: LEASE ALSO KNOWN AS TIMMONS-HENRICI #2. ALLIED CEMENTING COMPANY. KELLER TANK-WATE

Plugged through: CSG

District: 04

Signed

Roger H. Moses
(TECHNICIAN)

RECEIVED

10-26-2001
OCT 26 2001

KCC WICHITA

OCT 15 2001

INVOICED

Form CP-2/3

DATE

10-26-01

INV. NO.

2002060858

DIAMOND SHAMROCK
EXPLORATION COMPANY
P.O. BOX 400

#2 TIMMONS-HENRICI

10-7-20W
NE NW NE


AMARILLO, TX 79188-0001

CONTR BIG SPRINGS DRILLING

CTY ROOKS

GEOL DAVE TENEYCK

FIELD SLATE SW



ELV 2186 KB SPD 11/2/84
2182 GL

CARD ISSUED 1/24/85

IP D&A/ARB
11/8/84

SMP	Tops	Depth/Datum
SC	1746+ . 440
OREAD	3316-1130
HEEB	3368-1182
TOR	3391-1205
LANS	3406-1220
BKC	3608-1422
ARB	3643-1457
RTD	3678-1492

API 15-163-22,526

8 5/8 " 333/200SX

NO CORES

DST (1) 3462-3500 (LKC) / 30-60-30-60, REC 35' M, W/ TR OIL,
SIP 931-931#, FP 39-39 / 49-48#, HP 1764-1715#

DST (2) 3550-3618 (LKC) / 30-60-30-60, (1ST OP) WB BLDG TO
2 1/4 INCH FROM TOP OF BUCKET (2ND OP) WK SURF BLO
THRU-OUT, REC 45' OCM (5% OIL), SIP 119-119#, FP 59-59 /
59-59#

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

03010781

03010781

03010781